

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued February 5, 1968.

Operator's Full Name Braden Deem, Inc.

Complete Address: 210 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name Miller Well No. # 1

Location SE NW SE Sec. 36 Twp. 27 Rge. 15 (E) (W) W

County Pratt Total Depth 4702'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11:30AM Day 14th Month February Year 1968

The Above well was plugged as follows:

294' of 8 5/8" surface pipe, cemented with 300 sacks. 4647' of 5 1/2" long string, cemented with 200 sacks. Top perforation 4451'. Bottom of the hole was sanded to 4400', and cemented with 5 sacks, through the dump bailer, with cement from 4400' to 4360'. 2429' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 255', bridge plug and rock bridge from 255' to 245'. 13 sacks of cement was mixed in a barrel, and put on plug at 245', through the dump bailer and let set over-night. Next day hole was bailed dry, and 12 sacks of cement was added to the plug, with cement from 245' to 170'. Hole was filled with mud to 40' rock bridge from 40' to 30', and cemented with 10 sacks, with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-15-68

INV. NO. 7271-W

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1968
CONSERVATION DIVISION
Wichita, Kansas

Signed: Archie Elving
Well Plugging Supervisor