

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Braden-Deem Inc.

Complete Address 520-200 E 1st Wichita, Ks

Lease Name Morgan-White Well No. 1

Location NE/NE Sec. 35 Twp. 27 Rge. 15 (E) (W) W

County Pratt Total Depth 4816

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Co. Inc.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 5:00 PM Day 20 Month 11 Year 1970

The above well was plugged as follows:

413 ft of 8 5/8 surface pipe circulated. 4700 ft of 5 1/2 long string
cemented with 150 sacks. Top perf. at 4471-81 ft. Sand back to
4200 ft, 5 sacks cement with bailer. Pulled 3300 ft of 5 1/2. Set 10
ft. rock bridge at 300 ft. Fill hole with 5 yds of redimix to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED

Signed: E. Russell Biberstein
Well Plugging Supervisor

DATE 11-25-70

INV. NO. 2909-W