

15-119-10046-0000 51
5-23-88 R

1 020158

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 1/25/52
C NE NW, SEC. 26, T 33 S, R 30 W/E
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Novinger Unit Well # 503

Operator: Cities Service Oil & Gas Corporation
Name & Address 3545 N.W. 58th Street
Oklahoma City, OK 73112

County Meade 174.04

Well Total Depth 5355 feet

Conductor Pipe: Size 12 3/4 feet 637

Surface Casing: Size 8 5/8 feet 2694

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 3 p.m. Day: 19 Month: 5 Year: 19 88

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 405-854-6515

were: 5 1/2" at 5355' PBTD 5315' Perfs at 5274-5307'

1st plug set CIRP at 5000' with 4 sx cement on top,

2nd plug pump 50 sx cement at 2710-2610',

3rd plug pump 50 sx cement at 637-537',

4th plug pump 20 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 23 Month: 5 Year: 19 88

RECEIVED
STATE CORPORATION COMMISSION

ACTUAL PLUGGING REPORT 1st plug set CIRP at 5000' with 4 sx cement on top,

2nd plug pumped 50 sx cement at 2710-2610',

3rd plug pumped 50 sx cement at 637-537',

4th plug pumped 20 sx cement at 40-0'.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2734' of 5 1/2" casing and 1225' of 8 5/8".
(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired, check) observe this plugging.

DATE 7-13-88

Signed Glenn R Barlow
(TECHNICIAN)

REV. NO. 21305
5-23

AUG 3 1988