

1020147

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447Operator: Cities Service Oil & Gas Corporation County Meade 215.70

Name &

Address 3545 N.W. 58th StreetOklahoma City, OK 73112API NUMBER 15- Well Completion Date 12/12/50C NW NW, SEC. 26, T 33 S, R 30 W/E4620 feet from S section line4620 feet from E section lineLease Name Novinger Unit Well # 501Well Total Depth 6637 feetConductor Pipe: Size 13 3/8 feet 672Surface Casing: Size 9 5/8 feet 2714Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547Address Box 506, Liberal, KS 67901Company to plug at: Hour: 8 a.m. Day: 9 Month: 5 Year: 19 88Plugging proposal received from Don Horton(company name) Sargent's Casing Pulling Service (phone) 316-624-7455were: 5 1/2" at 5904' PBTD 5309' Perfs at 5270-90'1st plug set CIBP at 5010' and dump 2 sx cement on top,2nd plug pump 50 sx cement at 2700-2640', pull 5 1/2", shoot 9 5/8" off at 1206',3rd plug pull 9 5/8" to 700' and pump 50 sx cement at 680-600',4th plug pump 10 sx cement from 40-0'.Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)Plugging Operations attended by Agent?: All ☐ Part ☒ None ☐Operations Completed: Hour: 11:45 a.m. Day: 12 Month: 5 Year: 19 88ACTUAL PLUGGING REPORT 1st plug set CIBP at 5010' with 2 sx cement on top,2nd plug pump 50 sx cement at 2700-2640', pulled 5 1/2" and shot 9 5/8" off at 1206',3rd plug pulled 9 5/8" to 700' and pumped 50 sx cement at 680-600',4th plug pumped 10 sx cement from 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2717' of 5 1/2" & 1206' of 9 5/8" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED ~~XXXXXX~~ observe this plugging.DATE 5-18-88INV. NO. 20768Signed Glenn Barlow

(TECHNICIAN)