

15-119-10040-00015-18-88

387

1 020149

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Well Completion Date 6/6/51
C NE NE, SEC. 27, T 33 S, R 30 W/EX

TECHNICIAN'S PLUGGING REPORT

4620 feet from S section line
660 feet from E section line

Operator License # 5447

Lease Name Novinger Unit Well # 401

Operator: Cities Service Oil & Gas Corporation County Meade 195.10

Name & Address 3545 N.W. 58th Street

Well Total Depth 6003 feet

Oklahoma City, OK 73112

Conductor Pipe: Size 3 3/8 feet 653

Surface Casing: Size 9 5/8 feet 2686

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 14 Month: 5 Year: 19 88

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 5775' PBD 5748' Perfs at 5272-78'

1st plug set CIBP at 5010', 2nd plug pump 50 sx cement at 2700-2600',

3rd plug pump 50 sx cement at 670-570', 4th plug pump 20 sx cement at 40-0',

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 p.m. Day: 18 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5010',

RECEIVED
STATE CORPORATION COMMISSION

2nd plug pumped 50 sx cement at 2700-2600',

3rd plug pumped 50 sx cement at 670-570',

JUN - 3 1988

4th plug pumped 20 sx cement at 40-0'.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2814' of 5 1/2", 878' of 9 5/8".
(If additional description is necessary, use BACK of this form.)

INVOICED (if not) observe this plugging.

Signed Glenn R. Barlow
(TECHNICIAN)

DATE 6-27-88

INV. NO. 21042