

3-24-88 15-119-100 39-0001

1020129

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-4924

C SE SE, SEC. 27, T 33 S, R 30 W/EX

660 feet from S section line

660 feet from E section line

Lease Name Novinger Unit Well # 602W

County Meade 173.23

Well Total Depth 5330 feet

Conductor Pipe: Size 13 3/8 feet 600

Surface Casing: Size 8 5/8 feet 2714

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Cities Service Oil & Gas Corp.

Name & Address 3545 N.W. 58th Street

Oklahoma City, OK 73112

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 12:30 p.m. Day: 22 Month: 3 Year: 19 88

Plugging proposal received from Don Horton

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 5327' PBD 5303' Perfs at 5291-5302'

1st plug set CIBP at 3500' with 2 sx cement on top,

2nd plug perforate at 2700', run gel, mud and 50 sx cement,

3rd plug pump 40 sx cement at 630',

4th plug pump 20 sx cement at 40-0'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 24 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3500' with 2 sx cement on top,

2nd plug perforated at 2700', ran gel, mud and 50 sx cement,

3rd plug pumped 40 sx cement at 630',

4th plug pumped 20 sx cement at 40-0'.

Remarks: Used common cement by Sargents. Recovered 1623' of 5 1/2" casing and 1019' of 8 5/8".
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-5-88

WV. NO. 20288

3-24

Signed Glenn R. Barlow (TECHNICIAN)