

15-119-10038-0000 152
3-29-88

R

To: 1 020156
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-4924
C. NE SE, SEC. 27, T 33 S, R 30 W/EX

1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Novinger Unit Well # 601W

Operator: Cities Service Oil & Gas Corporation
Name & Address: 3545 N.W. 58th Street
Oklahoma City, OK 73112.

County Meade 173.06

Well Total Depth 5325 feet

Conductor Pipe: Size 13 3/8 feet 640

Surface Casing: Size 8 5/8 feet 2694

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9 a.m. Day: 25 Month: 3 Year: 19 88

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling (phone) 405-854-6515

were: 5 1/2" at 5325' PBD 5297' Perfs at 5280-92'

1st plug set CIBP at 5000' with 4 sx cement on top.

2nd plug pump 50 sx cement at 2720'.

3rd plug pump 50 sx cement at 670'.

4th plug pump 20 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 29 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5000' and dumped 4 sx cement

2nd plug pumped 50 sx cement at 2720'.

3rd plug pumped 50 sx cement at 670'.

4th plug pumped 20 sx cement at 40-0'.

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3210' of 5 1/2" casing and 1150' of 8 5/8".
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Glenn R. Barlow (TECHNICIAN)

DATE 7-13-88

WV. NO. 21306
3-29

AUG 3 1988