

15-119-10060-00-00

APR 29 1988

To: 1 020142
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 7/11/52
C NE NE SEC. 34, T 33 S, R 30 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: Cities Service Oil & Gas Corp.
Name & Address 3545 N.W. 58th Street
Oklahoma City, OK 73112

Lease Name Novinger Unit Well # 703
County Meade 193.38
Well Total Depth 5950 feet
Conductor Pipe: Size 13 3/8 feet 660
Surface Casing: Size 9 5/8 feet 2708

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 25 Month: 4 Year: 19 88

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 5360' PBTB 5303' Perfs at 5300-03'
1st plug set CIBP at 5010' with 2 sx cement on top,
2nd plug run 50 sx cement at 2710',
3rd plug run 50 sx cement at 650',
4th plug pump 20 sx cement at 40-0'

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 29 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5010' with 2 sx cement on top,
2nd plug pumped 50 sx cement at 2710',
3rd plug pumped 50 sx cement at 650',
4th plug pumped 20 sx cement at 40-0'.

Remarks: Used common cement by Sargent's recovered 2728' of 5 1/2" casing & 660' of 9 5/8".
(If additional details observed, use BACK of this form.)

INVOICED

DATE 5-17-88

INV. NO. 20627

RECEIVED
MAY 10 1988

Signed Glenn R. Barlow (TECHNICIAN)