

2-24-88 15-119-10056-00-00

To: 1 020122
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 4/1/54
C SE SE, SEC. 34, T 33 S, R 30 W/EX
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Novinger Unit Well # 901

Operator: Cities Service Oil & Gas Corp.
Name & Address 3545 N.W. 58th Street
Oklahoma City, OK 73112

County Meade 174.92
Well Total Depth 5382 feet
Conductor Pipe: Size 13 3/8 feet 781
Surface Casing: Size 9 5/8 feet 2693'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 1:45 p.m. Day: 22 Month: 2 Year: 1988

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 5380' PBSD 5302' Perfs at 5285-5300'

1st plug set CIBP at 5000' with 2 sx cement on top of plug,

2nd plug pump 50 sx cement at 2730',

3rd plug pump 50 sx cement at 800'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:15 p.m. Day: 24 Month: 2 Year: 1988

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5000' with 2 sx cement on top,

2nd plug ran 50 sx cement at 2730' - These plugs witnessed by Glenn Barlow.

3rd plug pumped 50 sx cement at 800'. James R. Kapp witnessed this plug.

Remarks: Used common cement by Sargent's. Recovered 2820' of 5 1/2" casing, 1225' of 9 5/8".
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 3-4-88

Signed Glenn D Barlow (TECHNICIAN)

INV. NO. 20011

2-24 MAR 24 1988