

15-119-10055-0000  
3-18-88

To: 1020128  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 7/3/52

C NW NW, SEC. 35, T 33 S, R 30 W/E

4620 feet from S section line

4620 feet from E section line

Lease Name Novinger Unit Well # 701

County Meade FKA: Vail # 174.43

Well Total Depth 5367 feet

Conductor Pipe: Size 13 3/8 feet 652

Surface Casing: Size 8 5/8 feet 2710

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Cities Service Oil & Gas Corp.

Name & Address 3545 N.W. 58th Street

Oklahoma City, OK 73112

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 1 p.m. Day: 15 Month: 3 Year: 19 88

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 5367' PBTD 5311' Perfs at 5280-96'

1st plug set CIBP at 3263' with 2 sx cement on top,

2nd plug 50 sx cement at cut off,

3rd plug pump 50 sx cement at 675',

4th plug pump 20 sx cement at 40'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4 p.m. Day: 18 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3263' with 2 sx cement on top,

2nd plug shot off at 2700', ran mud and 50 sx cement at cut off - 3/15/88,

3rd plug pumped 50 sx cement at 675' on 3/18/88,

4th plug pumped 20 sx cement at 40'.

Remarks: Used common cement by Sargent's. Recovered 2710' of 5 1/2" casing & 1232' of 8".  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1988  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED (City of xxxxxx) observe this plugging.

DATE 3-25-88

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 20184  
3-18