

To: 100074  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-175-21,368 21509-00-00  
NW SE NE, SEC. 18, T 33 S, R 33 W&E  
3830 feet from S section line  
1250 feet from E section line

TECHNICIAN'S PLUGGING REPORT 11-1  
Operator License # 6120  
Operator: Cabot Oil & Gas Corp.  
Name:  
Address 9400 N. Broadway, Ste. 608  
Oklahoma City, OK 73114

Lease Name Speakman Well # 2-18  
County Seward 94.93  
Well Total Depth 2921 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 554

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 12:30 p.m. Day: 1 Month: 11 Year: 19 96

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 2921' w/605 sx cement, PBD 2885', Perfs at 2586-92, 2658-78, 2614-23'  
GIBP at 2650', TOC 511'

1st plug pump 1 sx hulls and 20 sx cement,  
2nd plug pump 50 sx cement  
3rd plug at 40-0' with 10 sx cement.

11-6-96

RECEIVED  
KANSAS CORP COM  
NOV-6 11:4

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 1 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug spotted 20 sx cement with 2 sx hulls from 2586-2386'

Shot well at 472'. Cement on 8 5/8" X 4 1/2" 150' down.  
2nd plug ran tubing to 610' and pumped 20 sx cement,  
3rd plug filled backside to surface with 15 sx cement,  
4th plug pumped 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent & Horton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
(If ~~possible~~) observe this plugging.

DATE NOV 13 1996  
INV. NO. 46945

Signed Gary Alnter  
(TECHNICIAN)