

STATE OF KANSAS
STATE CORPORATION COMMISSION
30 S. Market, Room 2078
Topeka, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-21,5090000

LEASE NAME SPEAKMAN

WELL NUMBER 2-18

3830 Ft. from S Section Line

1250 Ft. from E Section Line

SEC. 18 TWP. 33 RGE. 33 (E) or (W)

COUNTY SEWARD

Date Well Completed 2/10/96

Plugging Commenced 10/30/96

Plugging Completed 11/04/96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CABOT OIL & GAS CORPORATION

ADDRESS 9400 N. BROADWAY, SUITE 608, OKLAHOMA CITY, OK 73114

PHONE# (405) 478-6500 OPERATORS LICENSE NO. 6120

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/31/96 (date)

by STEVE DURANT (KCC District Agent's Name).

Is ACO-1 filed? YES if not, is well log attached? _____

Producing Formation CHASE Depth to Top 2586' Bottom 2678' T.O. 2921'

show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	554'	--
				4-1/2"	2921'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
MIXED 1 SX HULLS & 20 SX CMT TO PLUG PERFS FROM 2586' TO 2386'. SHOT 4-1/2" @ 474', WOULD NOT PULL. SHOWED STUCK

APPROX 150'. RAN 2-1/16" TO 610' & MIXED 20 SX CMT, PLUG FROM 610' TO 410' IN 4-1/2". PUMPED 10 SX DOWN 4-1/2" & 8-5/8" ANNULUS FROM 40' TO 0' & PRESS UP TO 500 PSI. PUT 3 SX IN 4-1/2" FROM 40' TO 0'. CUT OFF & CAPPED 8-5/8" 3' BELOW GROUND LEVEL.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CABOT OIL & GAS CORPORATION

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

STEVE TURK

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Turk

(Address) 9400 N. BROADWAY, SUITE 608, OKC, OK 73114

SUBSCRIBED AND SWORN TO before me this 3RD day of DECEMBER, 19 96

Carole B. Turner
Notary Public

My Commission Expires: SEPTEMBER 2, 2000