

To: 1 100119 4-22 API NUMBER 15-189-21,243-00-03

STATE CORPORATION COMMISSION NE NE SW SW, SEC. 15, T 33 S, R 39 W/8

Wichita State Office Bldg. - PLUGGING SECTION 1250 feet from S section line  
130 S. Market, Room 2078 1250 feet from W 8 section line  
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT  
Operator License / 4549 Lease Name Texaco "A" Well # 1

Operator: Anadarko Petroleum Corporation County Stevens 212.88

Name: Address P.O. Box 351 Well Total Depth 6550 feet

Liberal, KS 67905-0351 Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1690

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 22 Month: 4 Year: 1997

Plugging proposal received from Kirby Lillard

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

work: 4 1/2" at 6264' w/255 sx cement, CIBP 5890', Perfs at 4848-62, 5976-6060, 6104-08'

1st plug pump 20 sx cement and 100 lbs. hulls at 2837',

2nd plug at 1710' with 50 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 p.m. Day: 22 Month: 4 Year: 1997

ACTUAL PLUGGING REPORT 1st plug spotted 20 sx cement and 200 lbs. hulls at 4680', displaced

with mud,

2nd plug spotted 90 sx cement at 985',

3rd plug pulled to 40' and spotted 10 sx cement.

Remarks: Used common cement by Sargents. Recovered 985' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Gary Winters (TECHNICIAN)

INVOICED

DATE APR 29 1997

INV. NO. 48037 4-22 JUL 11 1997

4-28-97 RECEIVED KANSAS CORPORATION