

1070098

TO: STATE CORPORATION COMMISSION

5-09

API NUMBER 15-129-21,580-00-00  
60'E C NE NW SEC. 18, T 33 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE  
WICHITA STATE OFFICE BLDG., 130 S. MARKET 2040 FEET FROM WEST SECTION LINE  
WICHITA, KANSAS 67202 LEASE NAME DAVISON "B" WELL # 3  
TECHNICIAN'S PLUGGING REPORT COUNTY MORTON 202,48  
OPERATOR LICENSE # 4549 WELL TOTAL DEPTH 6230 FEET  
OPERATOR: ANADARKO PETROLEUM CORP. PRODUCTION CSG: SIZE     @     ' WITH     SX  
NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8" @ 1657' WITH     SX  
ADDRESS LIBERAL, KS 67905-0351  
ABANDONED OIL WELL     GAS WELL     INPUT WELL     SWD WELL     D/A X  
OTHER WELL AS HEREINAFTER INDICATED    

PLUGGING CONTRACTOR NORSEMAN DRILLING, INC LICENSE NUMBER 3779  
ADDRESS 200 E FIRST, SUITE 307, WICHITA, KS 67202  
COMPANY TO PLUG AT: HOUR: 12:00 AM DAY: 09 MONTH: 05 YEAR: 1999  
PLUGGING PROPOSAL RECEIVED FROM JIM BARLOW  
(COMPANY NAME) NORSEMAN DRILLING, INC (PHONE) 316-265-9408

WERE:      
1ST PLUG AT 3000' WITH 100 SX CEMENT, 2ND PLUG AT 1680' WITH 50 SX CEMENT,  
3RD PLUG AT 500' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,  
5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,  
6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

    PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL     PART     NONE X  
OPERATIONS COMPLETED: HOUR: 3:00 AM DAY: 09 MONTH: 05 YEAR: 1999  
ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE  
1ST PLUG AT 3000' WITH 100 SX CEMENT, 2ND PLUG AT 1680' WITH 50 SX CEMENT,  
3RD PLUG AT 500' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,  
5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,  
6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

RECEIVED  
KANSAS CORPORATION COMMISSION  
6-9-99  
5-8-99  
6-2-99

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED Scott Alberg  
(TECHNICIAN) FORM CP-2/3

INVOICED  
DATE 6-9-99  
DIV. NO. 61010

Handwritten initials