

To: 1 100098 2-19  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 175-20,978 -0000

S/2 NE NW, SEC. 24, T 33 S, R 33 W/X  
4270 feet from S section line  
3280 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9953  
Operator: Harris Oil & Gas Company  
Name:  
Address 1125 17th St., Ste. 2290  
Denver, CO 80202-2037

Lease Name Boyer Trust Well # 1-24  
County Seward 20475  
Well Total Depth 6300 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1633

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 11 a.m. Day: 19 Month: 2 Year: 19 97  
Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

Work: 4 1/2" at 5975' w/150 sx cement, PBTD 6299', Perfs at 6216-20', TOC 4 1/2" @ 5485', TOC 3 1/2" @ 6040'  
1st plug pump 20 sx cement and 2 sx hulls to bottom,  
2nd plug at base of Hugoton, 3rd plug at 1660' with 50 sx cement,  
4th plug at 550' with 40 sx cement, 5th plug at 40' with 10 sx cement.

STATE CORPORATION COMMISSION  
FEB 25 1997

Plugging Proposal Received by Steve Middleton  
Wichita, Kansas  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_  
Operations Completed: Hour: 5 p.m. Day: 19 Month: 2 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement and 2 sx hulls on bottom,  
2nd plug pumped 30 sx cement at 2600-2500',  
3rd plug spotted 50 sx cement at 1660',  
4th plug spotted 40 sx cement at 550',  
5th plug spotted 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent & Horton. Recovered 2600' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I (and/or my agent) observe this plugging.

DATE 2-25-97

INV. NO. 47661

Signed Gay Winter  
(TECHNICIAN)

2-19 APR 25 1997