

To: 1 020824 11-23
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE SE NW NW, SEC. 27, T 33 S, R 33 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-21,065-0000

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

4030 feet from S section line
4030 feet from E section line
Lease Name Garey A Well # 1
County Seward 88.50
Well Total Depth 2723 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 609

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 3:30 p.m. Day: 22 Month: 11 Year: 19 94

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 2722' w/235 sx cement, PBTD 2713', Perfs at 2654-85, 2620-30, 2598-2607'
1st plug pump 2 sx hulls and 25 sx cement at perfs, pressure up, displace with mud,
2nd plug pump 50 sx cement at 540-400',
3rd plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4:45 p.m. Day: 23 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs. Pressured up
and displaced with mud,
2nd plug pumped 50 sx cement at 540-400',
3rd plug pumped 10 sx cement at 40 to -4'.
Could not pull at 540'-shot 460' free.

Remarks: Used common cement by Sargent & Horton. Recovered 460' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

Signed Glenn R. Barlow
(TECHNICIAN)

~~XXXXXX~~ observe this plugging.

INVOICED
DATE 12-6-94
INV. NO. 41811
11-23

RECEIVED
STATE CORPORATION COMMISSION
DEC 02 1994
CONSERVATION DIVISION
WICHITA, KANSAS