

To: 1020894 8-9
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-175-21,416-0000
SW SW NE SW, SEC. 27, T 33 S, R 33 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

1420 feet from S section line
1420 feet from WE section line
Lease Name Garey A Well # 2
County Seward 87.36
Well Total Depth 2688 feet
Conductor Pipe: Size 13 3/8 feet 655
Surface Casing: Size 8 5/8 feet 2600

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10:30 a.m. Day: 4 Month: 8 Year: 19 95

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

- work: 5 1/2" slotted liner at 2553-2688',
1st plug pump 4 sx hulls and 30 sx cement at perfs,
2nd plug shoot pipe, pump 50 sx cement at stub,
3rd plug pump 80 sx cement at 700',
4th plug pump 30 sx cement at 40'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____
Operations Completed: Hour: 10:15 a.m. Day: 9 Month: 8 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 4 sx hulls and 30 sx cement at perfs,
2nd plug shot pipe at 1596' and pumped 50 sx cement, pulled 210' and pipe stuck,
3rd plug shot pipe at 1160', could not pull. Shot pipe at 1040', pulled to 700' and
pumped 80 sx cement,
4th plug pulled remaining 8 5/8" and pumped 30 sx cement at 40' to -5'.

Remarks: Used common cement by Sargent & Horton. Recovered 1235' of 8 5/8".
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.
DATE 8-15-95
INV. NO. 43316

Signed Glenn R Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 1 1995
CONSERVATION DIVISION