

5-815-175-00156-0000

1020313

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App.  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 6/54

SE SE NW, SEC. 27, T 33 S, R 33 W X

2757 feet from S section line

2809 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5598

Lease Name Garey Well # 1-27

Operator: APX Corporation

County Seward 88.01

Name & Address P.O. Box 351

Well Total Depth 2708 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 566 w/275 sx

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor APX Corporation License Number 5598

Address P.O. Box 351, Liberal, KS 67905-0351

Company to plug at: Hour: 10 a.m. Day: 8 Month: 5 Year: 19 90

Plugging proposal received from Dave Gilmore

(company name) APX Corporation (phone) 316-624-6253

were: 7" at 2604' 5 1/2" slotted liner from 2575-2708' w/200 sx cement

1st plug pump 50 sx cement at 2700'

2nd plug pump 40 sx cement at 1580'

3rd plug pump 40 sx cement at 600'

4th plug pump 10 sx cement at 40'

Plugging Proposal Received by Mike Wilson (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:45 p.m. Day: 8 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug loaded hole with mud, pumped 50 sx cement at 2700',

hole squeezed and circulated cement to surface behind 7",

2nd plug pumped 40 sx cement at 1580',

3rd plug pumped 40 sx cement at 600',

4th plug pumped 20 sx cement at 40'.

Remarks: Used Class H common cement by Halliburton. No casing recovery. (If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 5-16-90

INV. NO. 28144

5-8

MAY 11 1990

CONSERVATION DIVISION

Signed Glen R Barber (TECHNICIAN)