

To: 1100028  
STATE CORPORATION COMMISSION

API NUMBER 15-175-21,420 -0000

Wichita State Office Bldg. PLUGGING SECTION NE NE SW SW, SEC. 33, T 33 S, R 33 W/E  
130 S. Market, Room 2078  
Wichita, KS 67202 3-14

1250 feet from S section line

1250 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Salley K Well # 1H

Operator: Anadarko Petroleum Corp.

County Seward 87.10

Address P.O. Box 351

Well Total Depth 2680 feet

Liberal, KS 67905-0351

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 674

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 2:30 p.m. Day: 14 Month: 3 Year: 1996

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

area: 5 1/2" at 2595' w/310 sx cement, Slotted liner 2557-2680', Perfs at 2600-80'

1st plug pump 2 sx hulls and 25 sx cement to bottom,

2nd plug pump hulls, 25 sx cement, spacer to 1600', 25 sx cement, spacer to 700', fill to

surface with cement.

Check cement on annulus.

Plugging Proposal Received by Steve Pfeiffer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 14 Month: 3 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls followed by 25 sx cement, displaced to 2600'-2400'.

2nd plug pumped gel spacer to 1600', 25 sx cement,

3rd plug pumped gel spacer to 700', 65 sx cement to surface,

4th plug pumped 15 sx cement on backside. Pressured to 1000 psi.

Remarks: Used common cement by Sargent & Horton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

**INVOICED**

DATE MAR 21 1996

INV. NO. 45101

Signed Gary Whenters (TECHNICIAN)

RECEIVED  
KANSAS CORP COM  
MAR 21 1996  
11:25