

15-175-21042-0001

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21042-00-01
Spot: NWSW Sec/Twnshp/Rge: 34-33S-33W
1980 feet from S Section Line, 660 feet from W Section Line
Lease/Unit Name: PRIEFERT C Well Number: 1H
County: SEWARD Total Vertical Depth: 6250 feet

Operator License No.: 4549 Conductor Pipe: Size feet: 203.13
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1564 CIRC.
Address: 1201 LAKE ROBBINS DRIVE Production: Size 4.5 feet: 3160 WITH 270 SX CMT
THE WOODLANDS, TX 77380 Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/19/2002 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE POND Company: ANADARKO PETROLEUM Phone: (852) 601-3130

Proposed Plugging Method: CIBP @ 2550' WITH 2 SX CMT. PRESSURE TEST CASING. PUMP CMT & CIRCULATE INSIDE & OUT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/19/2002 10:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:
PBTD 3065'. PERFS AT 2612-24, 2363-52, 2671-2705'. SET CIBP @ 2550' WITH 2 SX CMT ON TOP. PRESSURE TESTED CASING TO 500 PSIG, HELD OK. PERFORATE AT 1000'. PUMPED 350 SX CMT & CIRCULATE INSIDE & OUT FROM 1000' TO SURFACE.

RECEIVED
JAN 03 2003
KCC WICHITA

Remarks: USED CLASS H CMT BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
DEC 26 2002
KCC Dodge City

Signed Jim Holland (TECHNICIAN)

INVOICED
DATE 1-3-03
INV. NO. 2003061030

Form CP 3/3