

4-21-88 15-119-10033-9998

To: 1 020138
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-4924
C SE NW, SEC. 35, T 33 S, R 30 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

3300 feet from S section line

3300 feet from E section line

Operator: Cities Service Oil & Gas Corp.
Name & Address 3545 N.W. 58th Street
Oklahoma City, OK 73112

Lease Name Novinger Unit Well # 801W

County Meade 193.38

Well Total Depth 5950 feet

Conductor Pipe: Size 13 3/8 feet 645

Surface Casing: Size 9 5/8 feet 2708

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 4 p.m. Day: 18 Month: 4 Year: 19 88

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 5850' PBD 5347' Perfs at 5326-43'

1st plug set CIBP at 4300' with 2 sx cement on top,

2nd plug pump 50 sx cement at 2715',

3rd plug pump 50 sx cement at 505',

4th plug pump 20 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 21 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4300' with 2 sx cement on top,

2nd plug pumped 50 sx cement at 2715',

3rd plug loaded hole with mud and shot at 700', in cement, shot off at 511' and pumped 50 sx cement at 505',

4th plug pumped 20 sx cement at 40-0'.

STATE CORPORATION COMMISSION

APR 26 1988

Remarks: Used common cement by Sargent's. Recovered 2728' of 5 1/2" casing and 511' of 9 5/8".
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Glenn Barlow (TECHNICIAN)

DATE 4-27-88

V. NO. 20479