

15-119-10063-0000
3-12-88

1 020127

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 10/11/53

C NW SW, SEC. 35, T 33 S, R 30 W/EX

1980 feet from S section line

4620 feet from E section line

Lease Name Novinger Unit Well # 706

County Meade 175.50

Well Total Depth 5400 feet

Conductor Pipe: Size 13 3/8 feet 673

Surface Casing: Size 8 5/8 feet 2705

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Cities Service Oil & Gas Corp.

Name & Address 3545 N.W. 58th Street

Oklahoma City, OK 73112

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 10 Month: 3 Year: 19 88

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 5400' PBTD 5315' Perfs at 5290-5310'

1st plug set CIBP at 5000' with 2 sx cement on top,

2nd plug pump 50 sx cement at 2730',

3rd plug pump 50 sx cement at 700',

4th plug pump 20 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 p.m. Day: 12 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5000' with 2 sx cement on top

2nd plug pump 50 sx cement at 2730',

3rd plug pump 50 sx cement at 700',

4th plug pump 20 sx cement at 40-0'.

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2820' of 5 1/2" casing, 1214' of 8 5/8".
(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

DATE 3-21-88

NO. NO. 20137
3-12

Signed Glenn R Barlow (TECHNICIAN)