



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 8 1963

CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Paul Gattin of Anadarko Production Co. has this

date requested permission to plug the following described well:

Mr. Paul Gattin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351 Liberal, Kansas

Lease Name: Jarrett Well No. ^A 5-1

Location: C NE ^{SE} ME Sec. 22 Twp. 33 Rge. 33 (E) (W)

County Seward Total Depth 6232 Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Paul Gattin was instructed to plug the well as follows:

13 3/8" 62' Circulated w/cement 8 5/8" 1577' Circulated w/cement.

Mud 6232' to 2870' Spotted 90 Sax. cement 2870' to 2645'

Mud 2645' to 720' Spotted 45 Sax. cement 720' to 585'

Mud 585' to 45' Spotted 15 Sax. cement 45' to 5-

Very truly yours,

Hugh Scott
 Conservation Division Agent