

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 5 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Anadarko has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Kurth "A" Well No. 1

Location: C SW NE Sec. 22 Twp. 33 Rge. 33 (E) (W)

County: Seward Total Depth 6200' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1576' circulated w/ cement. 5 1/2" to 6199' cemented.


Top perforations 5704' Plug bottom w/ 25 sacks cement.

Top of cement 5550' Mud 5550' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

  
Conservation Division Agent