

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1970

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Casey of Coral Gas & Oil has this
date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: Coral Gas & Oil Inc.

Complete Address: 409 Bank of Southwest, Amarillo, Texas

Lease Name: Hunt Well No. 1

Location: C NW NW Sec. 23 Twp. 33 Rge. 33 (E) (W)

County: Seward Total Depth 6207' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Casey was instructed to plug the well as follows:

8 5/8" to 1550' corulated w/ cement. 4 1/2" 6163' cemented.

Top perforations 5701. Plug bottom w/ 20 sacks cement.

Top of cement 5512' Mud 5512' to 1600'

Spot 35 sacks cement 1600' to 1500' Mud 1500' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Evers
Conservation Division Agent