

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202


Dear Sir:

Mr. Sargent of Rains & has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.Operator's full Name: Rains & Williamson Oil Co. Inc.Complete Address: 475 Pg Ct, Wichita, KansasLease Name: Hunt Well No. 1Location: C NW NW Sec. 24 Twp. 33 Rge. 33 (E) (W)County: Seward Total Depth 6472' Oil WellGas Well Input Well SWD Well D & A Lost Hole Mr. Sargent was instructed to plug the well as follows:8 5/8" to 1594' circulated w/ cement. 4 1/2" to 5180' cemented.Top perforations 5060' Plug bottom w/ 20 sacks cement.Top of cement 4900' Mud 4900' to 1000'Spot 35 sacks cement 1000' to 900' Mud 900' to 45'Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent