

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Troy of Cities Service has this

date requested permission to plug the following described well:

Mr. Troy guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co.

Complete Address: 3545 N.W. 58th Street, Oklahoma City, Oklahoma

Lease Name: Novinger Flood Unit Well No. 704

Location: C SW NW Sec. 35 Twp. 33 Rge. 30 XX (E) (W)

County: Meade Total Depth 5380' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Troy was instructed to plug the well as follows:

13 3/8" to 640' circulated w/ cement. 8 5/8" to 2700' cemented.

5 1/2" casing to 5380' cemented. Top perforations 5289'

Plug bottom w/ 20 sacks cement Top of cement 5145'

Mud 5145' to 1600' Spotted 35 sacks cement 1600' to 1500'

Mud 1500' to 45' Plug, hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent