



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 12 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Lange of R.W. Lange has this  
date requested permission to plug the following described well:

Mr. Lange guarantees payment of the plugging fee.

Operator's full Name: R.W. Lange

Complete Address: Box 1034 Garden City, Kansas

Lease Name: Fox Well No. #2

Location: NE SW Sec. 36 Twp. 33 Rge. 30 (E)(W)

County Meade Total Depth 5879 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Lange was instructed to plug the well as follows:


8 5/8"-1472' Circulated w/cement. 5 1/2"-5790' Cemented.

Plug bottom w/25 Sax.cement top cement 5688' Mud 5688' to 700'

Spotted 35 Sax.cement 700' to 600' Mud 600' to 45'

Plug, 15 Sax.cement 45' to 0

Very truly yours,

  
Conservation Division Agent