

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1936
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Carnahan of Calvert Mid-America has this

date requested permission to plug the following described well:

Mr. Carnanhan guarantees payment of the plugging fee.

Operator's full Name: Calvert Mid-America

Complete Address: Box 911, Cushing, Oklahoma

Lease Name: Evans Well No. 1

Location: C NE SE Sec. 36 Twp. 33 Rge. 30 (X) (W)

County Meade Total Depth 6323' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Carnahan was instructed to plug the well as follows:

8 5/8" to 1373' circulated w/ cement. T.D. 6323'

Mud 6323' to 700' Spotted 35 sacks cement 700' to 600'

Mud 600' to 45' Plug, H^ulls & 15 sacks cement 45' to 0'.

Very truly yours,

E. Edward Jones
Conservation Division Agent