

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 5 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Anadarko Production Company

Complete Address Box 351, Liberal, Kansas

Lease Name Kurth "A" Well No. 1

Location C SW NE Sec. 22 Twp. 33 Rge. 33 (E) (W)

County Seward Total Depth 6200'

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 1 Month 9 Year 1973

The above well was plugged as follows:

8 5/8" to 1576' circulated w/ cement. 5 1/2" to 6199' cemented.

Top perforations 5704' Plug bottom w/ 25 sacks cement.

Top of cement 5550' Mud 5550' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 40'

Plug, Halls & 10 sacks cement 40' to 0' Company Pump

Pulled 2400' of 5 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 9-5-73

INV. NO. 7880-W

Signed: Edgar J. [Signature]  
Well Plugging Supervisor