

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Coral Gas & Oil Inc.

Complete Address 409 Bank of southwest Bldg., Amarillo, Texas

Lease Name Hunt Well No. 1

Location C NW NW Sec. 23 Twp. 33 Rge. 33 (E) (W)

County Seward Total Depth 6207

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated None

Plugging Contractor Daco Lease & Well Service

Address Borger, Texas License No. 138

Operation Completed: Hour 10:00AM Day 25 Month 11 Year 1970

The above well was plugged as follows:

8 5/8" to 1550' circulated w/ cement. 4 1/2" to 6163' cemented.

Top perforations 5701' Plug bottom w/ 20 sacks cement

Top of cement 5512' Mud 5512' to 1600'

Spotted 35 sacks cement 1600' to 1500' Mud 1500' to 45'

Plug. Halls & 15 sacks cement. 45' to 0'. Company Pump

Pulled 3481' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edward J. Evers  
Well Plugging Supervisor

INVOICED

DATE 12/1/70

INV. NO. 2940-w