

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION 100' N & 100' W of center

SEC. 23 TWP. 33 RGE. 33W

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well x

I have today completed supervision of plugging of:

Well No. C-1 Lease Hunt

Operator American Gas Prod. Co. Address Partlesville, Okla.

Field Hugoton County Seward

Total Depth 2770 Feet.

(Describe briefly the manner in which the well was plugged)

Tubing was cemented in hole while attempting to shut off water.

The casing was filled with heavy mud from the top of the cement (at 2227') to 20 feet below the surface. A wooden plug was driven in the 5 1/2" casing to 20' and the remainder was filled up with cement. A steel cap was welded on top of the 5 1/2" casing.

The rig was skidded 100'S & 100'E of center on same section.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 10 1951

CONSERVATION DIVISION  
Wichita, Kansas  
T. J. Phillips  
District Conservation Agent

Date April 21-1951

PLUGGING  
FILE SEC 23 T 33 R 33W  
BOOK PAGE 75 LINE 23