

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

15-175-20005-0000  
API NUMBER 15-

Sec. 26, T 33 S, R 33 W/E  
CNE-SW feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

feet from W/E section line

Operator License # 5469

Lease Name Salley "B" Well # 1

Operator: Anadarko Prod. Co.  
Name & Address Box 351  
Liberal Ks. 67901

County Seward

Well Total Depth 6270 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1584'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Sargents Casing License Number 6547

Address Box 506 Liberal Ks. 67901

Company to plug at: Hour: 12:00 PM Day: 10 Month: 1 Year: 19 83.

VERBAL PLUGGING ORDERS GIVEN TO Morgan Kershner

(company name) Sargents (phone) 316-624-9455

were: 4 1/2" @ 6270' P.B.T.P. 6232' Reys: 5812-5879'

Sand to 5750 + 4sx cement

Plug through 4 1/2" casing 1st plug @ 2350' w/ 50sx

2nd plug @ 1700' w/ 50sx 3rd plug @ 600' w/ 25sx

4th Bridge @ 40' -> cement to 0' w/ 10sx

Signed Paul Juttki (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:00 PM Day: 10 Month: 1 Year: 19 83

ACTUAL PLUGGING REPORT

Plugged as requested

Remarks:

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

JAN 14 1983

CONSERVATION DIVISION Wichita Kansas

Signed [Signature] (TECHNICIAN)

For Paul Juttki

FORM CP-2/3 Rev. 9-82

INVOICED  
DATE 2-7-83  
INV. NO. 2329-W