

15-119-10061-0000



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Cities Service Oil Co.
Complete Address 3545 N.W. 58th Street, Oklahoma City, Oklahoma 73112
Lease Name Novinger Flood Unit Well No. 704
Location G SW NW Sec. 35 Twp. 33 Rge. 30 (E) (W)
County Meade Total Depth 5380'
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Sargents Casing Pulling
Address Box 506, Liberal, Kansas License No. 511
Operation Completed: Hour 3:00PM Day 14 Month 1 Year 1974

The above well was plugged as follows:

13 3/8" to 640' circulated w/ cement. 8 5/8" to 2700' cemented.
5 1/2" to 5380' cemented. Top perforations 5289'
Plug bottom w/ 20 sacks cement Top of cement 5145'
Mud 5145' to 1600' Spotted 35 sacks cement 1600' to 1500'
Mud 1500' to 45' Plug, Hulls & 15 sacks cement 45' to 0'
Company Pump Pulled 2804' of 5 1/2" casing.

INVOLGED

I hereby certify that the above well was plugged as herein stated.

DATE 1/22/74
INV. NO. 8425-W

Signed: Edgar J. Eves
Well Plugging Supervisor