

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 18 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Troy of Cities Service Oil has this date requested permission to plug the following described well:

Mr. Troy guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co.

Complete Address: Box 1098, Liberal, Kansas

Lease Name: Novinger Well No. 502

Location: SW NW Sec. 26 Twp. 33 Rge. 30 NE (W)

County: Meade Total Depth 5904' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Troy was instructed to plug the well as follows:

13 3/8" to 664' circulated w/ cement. 9 5/8" to 2688' cemented.

5 1/2" to 5370' cemented. Top perforations 5272'

Plug bottom w/ 20 sacks cement. Top of cement 5100'

Mud 5100' to 2000' Spot 35 sacks cement 2000' to 1900'

Mud 1900' to 45' Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Green
Conservation Division Agent