

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1972

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Troy of Cities Service has this date requested permission to plug the following described well:

Mr. Troy guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co

Complete Address: Box 1098, Liberal, Kansas

Lease Name: Langhofer Well No. 402

Location: SE NE Sec. 27 Twp. 33 Rge. 30 (E) (W)

County: Meade Total Depth 5322' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Troy was instructed to plug the well as follows:

13 3/8" to 627' circulated w/cement. 8 5/8" to 2695' cemented.

5 1/2" to 5321' cemented. Top perforations 5277'

Plug bottom w/ 20 sacks cement. Top of cement 5100'

Mud 5100' to 2000' Spot 40 sacks cement 2000' to 1900'

Mud 1900' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent