



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 11 1964
 S-11-64
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Gattin of Anadarko Production Co. has this date requested permission to plug the following described well:

Mr. Gattin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Keller Well No. A-1

Location: C NW SE Sec. 16 Twp. 33 Rge. (E) (W) 33

County Seward Total Depth 6205' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gattin was instructed to plug the well as follows:

8 5/8"-1609' Circulated w/cement. 4 1/2"-6204' Cemented.

Perforations 6087' to 6093' Plug bottom w/25 Sax. cement top cement 5916'

Mud 5916' to 700' 35 Sax. cement 700' to 600'

Mud 600' to 45' Plug, 15 Sax. cement 45' to 0

Very truly yours,

[Signature]
 Conservation Division Agent