

State of Kansas



15-129-20036-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 9 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Hanna of Anadarko Production has this
date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351, Liberal, Kansas

Lease Name: Hayward "B" Well No. 1

Location: C SE NW Sec. 5 Twp. 33 Rge. 39 (E) (W)

County Morton Total Depth 6514' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hanna was instructed to plug the well as follows:

8 5/8" to 1673' circulated w/ cement. Mud 6514' to 1700'

Spotted 40 sacks cement 1700' to 1600' Mud 1600' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Evers
Conservation Division Agent