



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 27 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ipson of Ashland Oil has this date requested permission to plug the following described well:

Mr. Ipson guarantees payment of the plugging fee.

Operator's full Name: Ashland Oil & Refining Co.

Complete Address: Box 127, Satanta, Kansas

Lease Name: J.A. Christopher Well No. 1

Location: C NW Sec. 11 Twp. 33 Rge. 39 (E)(W)

County: Stevens Total Depth 2652' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ipson was instructed to plug the well as follows:

13 3/8" to 505' circulated w/ cement. 7" to 2440' cemented.

5 1/2" liner 2390' to 2652' Plug bottom w/ 25 sacks cement.

Top of cement 2340' Mud 2340' to 525'

Spot 55 sacks cement 525' to 400' Mud 400' to 30'

Plug, Hulls & 15 sacks cement 30' to 0'.

Very truly yours,

Edgar E. Jones
 Conservation Division Agent