



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

26 February 1982

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Doug Blair of Sargants Casing Pulling <sup>service</sup> has this date requested permission to plug the following described well:

Operator's Full Name: Anadarko Oil Co

Complete Address: Box 351 Liberal Kans (Dist) 67901

Lease Name: Schmidt Well No. B-1

Location: 1250' FSL - 1250' FWL Sec. 5 Twp. 3.3 Rge. 39 (E) (W)

County: Morton Total Depth: 6147'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: The well was completed but not produced

Mr. Blair was instructed to plug the well as follows:

There is 11654' of 8 3/4" surface casing cement circulated - 6142' of 4 1/2" production pipe plugged back to 5930'. The perforations were from 5875' to 5830'. 1st plug cemented off bottom hole with 20 bbl of cement. 2nd plug at 1150' with 50 bbl of cement. 3rd plug at 620' with 25 bbl of cement. 4th plug 40' to 0' with 10 bbl of cement. The plugging accomplished by Sargants casing pulling. The cement was pumped through production pipe with hole pulled fluid. They recovered 3627' of 4 1/2" production pipe.

Very truly yours,

Paul Luthin  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
3-9-82  
MAR - 9 1982  
CONSERVATION DIVISION  
Wichita Kansas