

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

15-175-20108-0001

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-175-20,108-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE TRAYLOR "A" WELL# 2 SEC. 2 T. 33S R. 31 (XXXX/West)

- C - SW - NW SPOT LOCATION/QQQQ COUNTY SEWARD

1980 FEET (in exact footage) FROM X/N (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM X/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1604' CEMENTED WITH 800 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 6059' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5555-5558'

ELEVATION -- T.D. 6060' PBDT 5600' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____
PROPOSED METHOD OF PLUGGING MIRU CSG PULLERS.RELEASE PKR & TOH W/2-3/8" TBG & PKR.TIH W/2-3/8" TBG.CIRC HOLE W/9 PPG MUD.SPOT 30 SX CLASS H CMT FROM 5400-5600'.TOH.PULL FREE POINT.CUT OFF 5-1/2" CSG.SPOT 20 SX CLASS H CMT AT CUT-OFF POINT.TOH W/5-1/2" CSG TO 1604'.SPOT 35 SX CLASS H CMT FROM 1604-1504'.TOH W/5-1/2" CSG TO 54'.SPOT 15 SX CLASS H CMT FROM 54-4'.CUT OFF 8-5/8" CSG 4' BELOW GL AND CAP.PERMANENTLY INSCRIBE THE DATE OF PLUGGING AND WELL NAME ON TOP OF CAP. RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? YES

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

JERRY RUTTMAN PHONE# (316) 624-6253

ADDRESS P.O. BOX 351 City/State LIBERAL, KANSAS 67905-0351

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-4-95 AUTHORIZED OPERATOR/AGENT: [Signature]

G.L. ASHTON (signature) DIV. PRODUCTION REGULATION

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1995
CONSERVATION DIVISION
KANSAS



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

April 7, 1995

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Traylor "A" #2
API 15-175-20,108
1980 FNL 660 FWL
Sec. 02-33S-31W
Seward County

Dear Jerry Ruttman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760



JAMES L. ASHTON
DIVISION PRODUCTION MANAGER

April 6, 1995

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

Attn: Priscilla Zadoka


Re: Plug and Abandonment
Well Plugging Application Form (Form CP-1)
Traylor "A" No. 2
Section 2-33S-31W
Seward County, Kansas

Dear Ms. Zadoka:

Enclosed in duplicate is the "Well Plugging Application" (KCC Form CP-1) submitted for your approval to plug and abandon the subject well.

Upon approval of this application, please notify Anadarko's Liberal office at the letterhead address so that operations may commence.

Very truly yours,


J. L. Ashton
Division Production Manager
LB/sh

Enclosures

cc: Well File
Ken Lester - HGO
Manager Land Administration - HGO
Ellen Cobb - HGO
WI Owners

RECEIVED
STATE CORPORATION COMMISSION

APR - 7 1995

CONSERVATION DIVISION
WICHITA, KANSAS