

KANSAS

W
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

DEC 7 - 1972

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Diamond Shamrock Corporation

Complete Address Box 631, Amarillo, Texas 79105

Lease Name Pauline V. Hulburt Well No. 1

Location NE NE NE Sec. 5 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5649'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 11:00AM Day 4 Month 12 Year 1972

The above well was plugged as follows:

9 5/8" to 2676' circulated w/ cement. 7" to 5647' cemented.

Top perforations 5581' Plug bottom w/ 25 sacks cement.

Top of cement 5400' Mud 5400' to 900'

Spotted 10 sacks cement 900' to 800' Mud 800' to 45'

Plug. Halls & 15 sacks cement 45' to 0'. Company Pump

Pulled 3253' of 7" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward A. Ellis*
Well Plugging Supervisor

INVOICED

DATE 12/7/72
INV. NO. 6902-W