

ORIGINAL

CONFIDENTIAL

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

WELL NAME: PERRY A-2  
C-NE/4 SEC 4-33S-38W  
STEVENS COUNTY KANSAS

KCC

JUN 29

CONFIDENTIAL

COMMENCED: 3-06-94  
COMPLETED: 3-18-94  
OPERATOR: ANADARKO PETROLEUM CORP.

DEPTH From	To	FORMATION	REMARKS
0	425	Sand-Clay	
425	1168	Redbed-Gyp	
1168	1382	Sand	Ran 41 jts of 24# 8.5/8" csg set @ 1707' w/600 sks
1382	1708	Redbed-Gyp	class H 50/50 Posmix 4%
1708	2035	Anhy-Shale	Gel 2%CC 1/4 # Floseal
2035	2680	Shale-Lime	200 sks Common 2%CC
2680	6260	Lime-Shale	PD@ 3:30 PM 3-7-94

RELEASED

6260 - TD

JUL 26 1995

FROM CONFIDENTIAL

Ran 142 jts of 15 1/2# 5 1/2" csg set @ 6258' w/FO tool @ 3107 - Top w/50sks 65/35 Posmix 1/4# Cellophar Flakes - 155 sks Thixset Premium 1/4# Cellophane Flakes  
PD @ 5:15 PM 3-18-94  
RR 6:15 PM 3-18-94

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 05 1994

CONSERVATION DIVISION  
WICHITA, KS

STATE OF KANSAS  
COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

*[Signature]*  
James S. Sutton, II - President

Subscribed & sworn to before me this 21<sup>st</sup> day of March, 1994

*[Signature]*  
Shirley A. Pelz, Notary Public

My commission expires October 18, 1997

