

GABBERT-JONES, INC.
WICHITA, KAS.

DRILLERS WELL LOG

GUYER "A" - 3H
50'N of C E/2 Sec. 3-33S-38W
Stevens County, Kansas

COMMENCED: 6-12-87

COMPLETED: 6-16-87

OPERATOR: PAN EASTERN EXPLORATION COMPANY

DEPTH		Formation	Remarks
From	To		
0	615	Sand - Redbed	Ran 14 jts. of 24# 8 5/8" csg.
615	1160	Redbed	LD @ 610' w/210 sks 75/25 Posmix
1160	1353	Glorietta Sand	2% CC - 1/4# Floseal - 150 sks
1353	2281	Shale	Common - 3% CC - 1/4# Floseal
2281	2473	Shale - Lime	PD @ 2:00 AM 6-13-87
2473	2882	Lime - Shale	
	2882 TD		Ran 69 jts. of 14# 5 1/2 " csg.
			LD @ 2881 w/195 sks class C
			20% DCD - 2% CC - 1/4# Floseal
			40 sks Class C - 10% DCD
			2% CC - 1/4# Floseal
			PD @ 12:45 AM 6-16-87

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1987

RELEASED

CONSERVATION DIVISION
Wichita, Kansas


OCT 20 1988

FROM CONFIDENTIAL


STATE OF KANSAS)
)
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.


James S. Sutton, II - President

Subscribed & sworn to before me this


Lola Lenore Costa - Notary Public

SEP 24 1987

My Commission expires 11-21-88

KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH