

FINCHAM "G" 1H
 SEC. 33-33S-34W
 SEWARD CO., KS

GABBERT-JONES, INC.

Drillers Well Log

COMMENCED: 8-26-89

COMPLETED: 8-29-89

OPERATOR:

APX CORPORATION

DEPTH		FORMATION	REMARKS
From	To		
0	140	Sand - Clay	Ran 16 jts of 24# 8 5/8" csg set @ 680' w/275 sks 25/75 Posmix - 2% CC - 1/4# CF 150 sks Common - 3% CC 1/4# CF PD @ 10:30 PM 8-26-89.
140	1170	Clay - Redbed	
1170	1322	Glorietta Sand	
1322	2570	Shale	
2570	2863	Shale - Lime	
	2863 TD		Ran 67 jts of 14# 5 1/2" csg set @ 2858' w/195 sks Class C - 20% DCD - 2% CC 1/4# CF - 40 sks Class C 10% DCD - 2% CC - 1/4# CF PD @ 4:00 AM 8-29-89. RR @ 5:00 AM 8-29-89.

RECEIVED
 STATE COMMISSION

JAN 16 1990

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS]
]
 COUNTY OF SEDGWICK]

I, the undersigned, being duly sworn on oath,
 state that the above Drillers Well Log is true
 and correct to the best of my knowledge and
 belief and according to the records of this office.

GABBERT- JONES, INC

[Signature]
 James S. Sutton, II - President

Subscribed & sworn to before me this
 5th day of SEPTEMBER, 1989.

[Signature]
 Lola Lenore Costa

My commission expires Nov. 21, 1992

LOLA LENORE COSTA
 NOTARY PUBLIC
 STATE OF KANSAS
 My Appt. Exp. 11/21/92