

BARRETT 1H
SEC. 31-33S-34W
SEWARD COUNTY, KS

GABBERT-JONES, INC.

Drillers Well Log

COMMENCED: 9-1-89

COMPLETED: 9-3-89

OPERATOR: ANADARKO PETROLEUM CORP. R-11

DEPTH		FORMATION	REMARKS	
From	To			
0	710	Sand-Clay	Ran 17jts of 24# 8 5/8" csg set @ 706' w/275 sks 25/75 Posmix - 2%CC - 1/4# CF 150 sks Common - 3%CC 1/4#CF PD @ 8:45PM 9-1-89	
710	1197	Redbed		
1197	1353	Glorietta Sand		
1353	1360	Shale		
1360	2070	Redbed-Shale		
2070	2432	Redbed-Shale-Lime		
2432	2772	Shale-Lime		
2772	2885	Lime-Shale		
2885 - TD				Ran 67jts of 14# 5 1/2" csg set A 2881' w/195 sks class C 20%DCD - 2%CC- 1/4#CF 40sks class C- 10%DCD 2%CC- 1/4#CF PD @ 10:00PM 9-3-89 RR @ 11:00 PM 9-3-89

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1990
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS]
]
COUNTY OF SEDGWICK]

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton, II
James S. Sutton, II - President

Subscribed & sworn to before me this
6th day of Sept, 1989.

Lola Lenore Costa
Lola Lenore Costa

LOLA LENORE COSTA
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 11/21/92

My commission expires Nov. 21, 1992