

CONFIDENTIAL

ORIGINAL

GABBERT-JONES, INC.
WICHITA, KANSAS

- DRILLERS' WELL LOG -

WELL NAME: Loflin "A" #2
Sec 1-33S-38W
Stevens County, Kansas

API#15-189-21778-00-00

COMMENCED: 9/3/94
COMPLETED: 9/16/94
OPERATOR: Anadarko Petroleum Corp.

| DEPTH | | FORMATION | REMARKS |
|-------|---------|------------|---------------------------|
| From | To | | |
| 0 | 560 | Sand-Clay | |
| 560 | 600 | Redbed | Ran 41 jts of 24# 8 5/8" |
| 600 | 1145 | Redbed-Gyp | csg set @ 1706' w/600 sks |
| 1145 | 1360 | Sand | Class H 50/50 Posmix |
| 1360 | 1707 | Redbed-Gyp | 4% Gel 2% CC 1/4# Flocele |
| 1707 | 2165 | Anhy-Shale | 200 sks Common 2% CC |
| 2165 | 2685 | Shale-Lime | PD @ 12:15PM 9/5/94 |
| 2685 | 6270 TD | Lime-Shale | |

RELEASED

JAN 11 1996

FROM CONFIDENTIAL

Ran 144 jts of 15 1/2# 5 1/2"
csg set @ 6194' w/DV
Tool @ 3363 .bottom w/
50 sks Class H 65/35
Posmix 190 sks Thixset
1/4# Flocele
PD @ 7:45AM 9/16/94
2nd stage w/50 sks
Class C 20% Diecel D
1/4# Flocele 50 sks Class C
10% Diecel D 1/4# Flocele
JC @ 12:30PM 9/16/94
RR @ 1:30PM 9/16/94


STATE OF KANSAS]
COUNTY OF SEDGWICK]


I, the undersigned, being sworn on oath, state that the above Drillers' Well log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.


James S. Sutton, II President

Subscribed & sworn to before me this 21st day of September, 1994


Shirley A. Pelz, Notary Public
My commission expires: October 18, 1997



RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1994
CONSERVATION DIVISION
WICHITA, KANSAS