

GABBERT-JONES, INC.
WICHITA, KAS.

DRILLERS WELL LOG

ETZOLD UNIT NORTH #3-6
C SW/4 Sec. 22-33S-34W
SEWARD COUNTY, KANSAS

COMMENCED: 1-9-87

COMPLETED: 1-21-87


OPERATOR: ANADARKO PETROLEUM CORPORATION

DEPTH			
From	To	Formation	Remarks
0	30	Cased hole	30' of 20" csg.
30	150	Surface Sand-Clay	
150	550	Sand-Clay	Ran 40 jts. of 24# 8 5/8"
550	650	Redbed	Csg. LD @ 1635' w/575
650	1200	Redbed-Anhy-Sand	sks. 50/50 Posmix 4% Gel
1200	1638	Redbed-Sand-Anhy	2% CC - 200 sxs. Common
1638	1875	Anhy-Shale	2% CC
1875	2300	Shale	PD @ 6:45 PM 1-10-87
2300	2555	Shale-Lime	
2555	5300	Lime-Shale	Ran 152 jts. of 15 1/2#
5300	5395	Lime	5 1/2" csg. LD @ 6424' w/
5395	6170	Lime-Shale	50 sks. lite - 1/2# Celoflake
6170	6330	Lime-Sand	100 sks. 50/50 Posmix 10% Salt
6330	6425	Lime-Shale	1/4# Celoflake. PD @ 3:30 PM 1-21-87

6425 TD


STATE OF KANSAS)
)
 COUNTY OF SEDGWICK) I, the undersigned, being duly sworn on oath, state that
 the above Drillers' Well Log is true and correct
 to the best of my knowledge and belief and according
 to the records of this office.

GABBERT-JONES, INC.



James S. Sutton, II - President

Subscribed & sworn to before me this 29th day of January 1987



Lola Lenore Costa - Notary Public

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1987

My Commission expires November 21, 1988

CONSERVATION DIVISION
Wichita, Kansas