

15-175-20966-0000
BW

GABBERT-JONES, INC.
WICHITA, KAS.

DRILLERS WELL LOG

ETZOLD UNIT N 2-5
3960' FSL & 2690' FEL
Sec. 22-33S-34W
Seward County, Kansas

COMMENCED: 8-7-87

COMPLETED: 8-21-87

OPERATOR: ANADARKO PETROLEUM CORP.

DEPTH			
From	To	Formation	Remarks
0	671	Sand-Clay	
671	1120	Sand-Redbed	
1120	1295	Glorita	Ran 39 jts. of 24# 8 5/8" csg
1295	1752	Redbed	LD @ 1627' w/550 sks 50/50
1752	2948	Shale	Posmix - 4% Gel - 2% CC
2948	3460	Shale-Lime	200 sks Class H - 2% CC
3460	6245	Lime	PD @ 11:35 AM 8-8-87.
6245	6420	Sand-Lime	
	6420 TD		Ran 157 jts of 15 1/2# 5 1/2" csg LD @ 6416' w/50 sks Hocolite - 100 sks 50/50 Posmix 1/4# Gilsonite. P D @ 3:30 AM. 8-21-87.


RELEASED

DEC 12 1988

FROM CONFIDENTIAL

STATE OF KANSAS)
)
COUNTY OF SEDGWICK) I, the undersigned, being duly sworn on oath, state that
the above Drillers' Well Log is true and correct
to the best of my knowledge and belief and according
to the records' of this office.

GABBERT-JONES, INC.


James S. Sutton, II - President

NOV 13 1987

Subscribed & sworn to before me this 26th day of August 1987.


Lola Lenore Costa - Notary Public

My Commission expires 11-21-88