

ORIGINAL

KANSAS DRILLERS LOG

S. 20 T. 33 S. R. 34 ^E/_W

API No. 15 — 175 — 20379-00-00
County Number

Loc. NW SE

County Seward

Operator
Anadarko Production Company

Address
Box 351 Liberal, KS 67901

Well No. 1 Lease Name
Guttridge D.


Footage Location
1830 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor Geologist
Lohmann-Johnson Drlg. Co. Joseph G. Blair, Jr.

Spud Date Total Depth P.B.T.D.
10-27-78 6346 6300

Date Completed Oil Purchaser
12-18-78 Murphy Oil Corp.

640 Acres
N



Locate well correctly

Elev.: Gr. 2928.4

DF _____ KB _____

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"	24	1698'	Common Poz	200 500	3% CACL 4% Gel & 2% CACI
Production	7 7/8"	5 1/2"	15.5	6342	Poz	200	.5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		6272-82

Size	Setting depth	Packer set at
2 3/8	6291	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/1000 gal 10% NE + 25 BS	6272-82
F/22000 gal 40# Versa gel + 39000 # 20-40 Snd	6272-82

INITIAL PRODUCTION

Date of first production 12-3-78		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 4 bbls.	Gas TSTM MCF	Water 3 bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s) 6272-82		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 65217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDOW, ETC.:
Well No. 1	Lease Name Guttridge D	Oil
S 20 T 33S R 34 ^X / _W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	40'	123'		
Sand & Redbed	123'	1675'		
Redbed & Shale	1675'	2376'		
Lime & Shale	2376'	6346'		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Paul Campbell <small>Signature</small>
	Division Production Manager
	<small>Title</small>
	January 15, 1979
	<small>Date</small>